



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in

Quotation No. 33/Repair cum Maint. of Toilet of 2025-26(VP)

Dated, Bishnupur, the: 31 / 12 /2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Bankati Mouza, J.L. No.- 123 (N 23°02'51.27" & E 087°17'12.99"), of Bishnupur-I Beat, Bishnupur Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-1)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Bishnupur	Bishnupur-I	Bankati Mouza, J.L. No.- 123	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2353 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA BANKATI JL. NO- 123,
UNDER BISHNUPUR-I BEAT OF BISHNUPUR RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.**

SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
			TOTAL			30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
			TOTAL			7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado,window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
			TOTAL			11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
	1 0.900 1.800	1.620			
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Supplying, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					

ANUP MAITRA
(Reg.-01293) D.C.E.
Khatra, Bankura


Divisional Forest Officer,
Panchet Division, Bankura



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 34/Repair cum Maint. of Toilet of 2025-26(VP)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Jamunabandh Mouza, J.L. No.- 97 (N 23°03'46.9" & E 087°17'58.9"), of Bishnupur-I Beat, Bishnupur Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-2)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Bishnupur	Bishnupur-I	Jamunabandh Mouza, J.L. No.- 97	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2354 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:


1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA JAMUNABANDH JL. NO-97, UNDER BISHNUPUR-I BEAT OF BISHNUPUR RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.									
SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
				TOTAL		30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
				TOTAL		7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
				TOTAL		11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
		1	0.900		1.800
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/lt.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/lt.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/lt.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANIL KHATRA
 (Reg.-01293) D.C.E.
 Khatra, Bankura


Divisional Forest Officer,
 Panchet Division, Bishnupur.



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 35/Repair cum Maint. of Toilet of 2025-26(JP)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Padumpur Mouza, J.L. No.- 14 (N-23°03'52.12"& E-87°26'31.89"), of Joypur Beat, Joypur Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-3)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Joypur	Joypur	Padumpur Mouza, J.L. No.- 14	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2355 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA PADUMPUR JL. NO- 14, UNDER JOYPUR BEAT OF JOYPUR RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.									
SL NO	DESCRIPTION OF ITEM				QTY	UNIT	RATE(Rs.)		AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average				66.000	SQM	19.00		1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corrigen page-49 sl-1)								
	i) OUTER SIDE				30.450				
	TOTAL				30.450	m ²	153.00		4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corrigen page- 49 sl-1)								
	i) INNER SIDE				11.600				
	TOTAL				11.600	m ²	135.00		1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corrigen page-49 sl-1)								
	i) roof slab				4.320				
	ii) CHAJJA FOR DOOR BOTH SIDE				1.125				
	iii) CHAJJA FOR WINDOW BOTH SIDE				0.675				
	iv) stair				1.688				
	TOTAL				7.808	m ²	122.00		952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado				7.200				
	ii) outside dado				3.150				
	iii) stair				0.938				
	TOTAL				11.288	sqm	34.00		383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)				
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel								
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles &rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16								
		1	0.900		1.800	1.620			
	TOTAL		1.620	sqm	2438.00	3949.56			
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)								
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858							
	TOTAL		49.858	m²	67.00	3340.49			
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00				

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANUP KUMAR
 (Reg.-01293) D.C.E.
 Ichatra, Bankura


Divisional Forest Officer,
 Panchet Division, Bishnupur.



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 36/Repair cum Maint. of Toilet of 2025-26(JP)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Padumpur Mouza, J.L. No.- 14 (N-23°04'20.62" & E-87°26'14.87"), of Joypur Beat, Joypur Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-4)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Joypur	Joypur	Padumpur Mouza, J.L. No.- 14	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address** should be properly mentioned on the **envelope**. **Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2356 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA PADUMPUR JL. NO- 14,
UNDER JOYPUR BEAT OF JOYPUR RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.**

SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
			TOTAL			30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
			TOTAL			7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
			TOTAL			11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelamated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/lt.no-16				
		1	0.900		1.800
		TOTAL		1.620	sqm
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/lt.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
		TOTAL		49.858	m²
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/lt.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					

ANUP MISHRA
(Reg.-01293) D.C.E.
Katra, Bankura


Divisional Forest Officer,
Panchet Division, Bishnupur.



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 37/Repair cum Maint. of Toilet of 2025-26(JP)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Jangalmahal Mouza, J.L. No.- 85 (N-23°03'39.53" & E-87°23'15.89"), of Machantala Beat, Joypur Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-6)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Joypur	Machantala	Jangalmahal Mouza, J.L. No.- 85	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2357 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA JANGALMAHAL JL. NO-85, UNDER MACHANTALA BEAT OF JOYPUR RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.

SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
	TOTAL					30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
	TOTAL					11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
	TOTAL					7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
	TOTAL					11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)				
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel								
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16								
		1	0.900		1.800	1.620			
	TOTAL				1.620	sqm	2438.00	3949.56	
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)								
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)			49.858					
	TOTAL		49.858	m²	67.00	3340.49			
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00				

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					

ANUP KATIA
(Reg.-01293) D.O.E.
Katra, Bankura


Divisional Forest Officer,
Panchet Division, Bishanpur.



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in

Quotation No. 38/Repair cum Maint. of Toilet of 2025-26(BKD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Uporsole Mouza, J.L. No.- 156(93) (N-22°58'49.7" & E-87°24'14.4"), of Uporsole Beat, Bankadaha Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-8)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Bankadaha	Uporsole	Uporsole Mouza, J.L. No.- 156(93)	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2358 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.


Divisional Forest Officer,
Panchet Division, Bishnupur

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA UPORSOLE JL. NO-156,(93) UNDER UPORSOLE BEAT OF BANKADAHA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.									
SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
			TOTAL			30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
			TOTAL			7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
			TOTAL			11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
	1 0.900 1.800	1.620			
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m ²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/ 2009 and 1729/ 2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and boalts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					

ANUT MARIADA
(Reg.-01293) D.C.E.
Ichatra, Bankura



Divisional Forest Officer
Panchet Division, Bishnupur



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in

Quotation No. 39/Repair cum Maint. of Toilet of 2025-26(BKD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Amdangra Mouza, J.L. No.- 130 (N-22°57'11.5" & E-87°15'48.0"), of Peardoba Beat, Bankadaha Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-9)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Bankadaha	Peardoba	Amdangra Mouza, J.L. No.- 130	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2359 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

C D T-9

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA AMDANGRA JL. NO- 130, UNDER PEARDOBA BEAT OF BANKADHA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.									
SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average					66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE					1	10.500		2.900
	TOTAL					30.450			
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page- 49 sl-1)								
	I) INNER SIDE					1	4.000		2.900
	TOTAL					11.600	m ²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab					1	2.400	1.800	4.320
	ii) CHAJJA FOR DOOR BOTH SIDE					2	1.250	0.450	1.125
	iii) CHAJJA FOR WINDOW BOTH SIDE					2	0.750	0.450	0.675
	iv) stair					3	0.450	1.250	1.688
	TOTAL					7.808	m ²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado					1	3.000	2.400	7.200
	ii) outside dado					1	10.500		0.300
	iii) stair					1	1.250		0.750
	TOTAL					11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/lt.no-16				
	1 0.900 1.800	1.620			
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/lt.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m ²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/lt.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/ 2009 and 1729/ 2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANUR KHATWALA
 (Reg.-01293) D.C.E.
 Ichatra, Bankura


Divisional Forest Officer
 Panchet Division, Bishnupur



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 40/Repair cum Maint. of Toilet of 2025-26(BKD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Chitrang Mouza, J.L. No.- 137 (N-22°58'30.3" & E-87°20'40.8"), of Bankadaha Beat, Bankadaha Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-11)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Bankadaha	Bankadaha	Chitrang Mouza, J.L. No.- 137	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2360 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA CHITRANG JL. NO- 137,
UNDER BANKADAHA BEAT OF BANKADAHA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.**

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10				
	Quarter Average				
	TOTAL	66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)				
	i) OUTER SIDE	1	10.500	2.900	30.450
	TOTAL	30.450	m ²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)				
	i)INNER SIDE	1	4.000	2.900	11.600
	TOTAL	11.600	m ²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)				
	i) roof slab	1	2.400	1.800	4.320
	ii)CHAJJA FOR DOOR BOTH SIDE	2	1.250	0.450	1.125
	iii)CHAJJA FOR WINDOW BOTH SIDE	2	0.750	0.450	0.675
	iv) stair	3	0.450	1.250	1.688
	TOTAL	7.808	m ²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15				
	i) flooring with dado	1	3.000	2.400	7.200
	ii) outside dado	1	10.500	0.300	3.150
	iii) stair	1	1.250	0.750	0.938
	TOTAL	11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminated Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S.frame sh all have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
	1 0.900 1.800	1.620			
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I)SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m ²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials ,jointing materials, cutting pipes, making threads ,cutting trenches upto 1.5 metre below surface in all sortsof soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II)Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/lt.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/lt.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/lt.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					

ANUP KATADA
(Reg.-012553) D.O.E.
Ichtra, Bankura



Divisional Forest Officer
Panchet Division, Bishnupur



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in

Quotation No. 41/Repair cum Maint. of Toilet of 2025-26(TD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Chenchuria Mouza, J.L. No.-70 (N-23°01'13.5" & E-87°05'59.2"), of Taldangra Beat, Taldangra Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-13)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Taldangra	Taldangra	Chenchuria Mouza, J.L. No.-70	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2361 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.


Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA CHENCHURIA JL. NO- 70,
UNDER TALDANGRA BEAT OF TALDANGRA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.**

SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corrigien page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
			TOTAL			30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corrigien page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corrigien page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
			TOTAL			7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
			TOTAL			11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminate Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th., 20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th. x 15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardware as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
	1 0.900 1.800	1.620			
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I) SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m ²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sort of soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II) Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/ 2009 and 1729/ 2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid seperately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/lt.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and boalts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/lt.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/lt.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANIL KHATRA
 (Reg.-01293) D.O.E.
 Khatra, Bankura


Divisional Forest Officer
 Panchet Division, Bishnupur



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 42/Repair cum Maint. of Toilet of 2025-26(OD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Dhaboni Mouza, J.L. No.-50 (N-23°04'56.90" & E-087°07'35.61"), of Chingani Beat, Onda Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-14)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Onda	Chingani	Dhaboni Mouza, J.L. No.-50	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2362 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA DHABONI JL. NO- 50, UNDER CHINGANI BEAT OF ONDA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.									
SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average					66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE					1	10.500		2.900
	TOTAL					30.450			
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page- 49 sl-1)								
	I) INNER SIDE					1	4.000		2.900
	TOTAL					11.600	m ²	153.00	4658.85
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab					1	2.400	1.800	4.320
	ii) CHAJJA FOR DOOR BOTH SIDE					2	1.250	0.450	1.125
	iii) CHAJJA FOR WINDOW BOTH SIDE					2	0.750	0.450	0.675
	iv) stair					3	0.450	1.250	1.688
	TOTAL					7.808	m ²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado					1	3.000	2.400	7.200
	ii) outside dado					1	10.500		0.300
	iii) stair					1	1.250		0.750
	TOTAL					11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminate Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th., 20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th. x 15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardware as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
		1	0.900		1.800
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I) SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m ²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sort of soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II) Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANIL KUMAR
 (Reg.-01293) D.C.E.
 Ichatra, Bankura


Divisional Forest Officer
 Panchet Division, Bishnupur



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 43/Repair cum Maint. of Toilet of 2025-26(OD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair cum Maint. of Toilet (1 No.) at Dhaboni Mouza, J.L. No.-50 of Chingani Beat, Onda
Range under Panchet Division. (On Contract)

Copy of Estimate Enclosed (CDT-15)

Range	Beat	Mouza & J.L	Quantity	Project Cost
Onda	Chingani	Dhaboni Mouza, J.L. No.-50	01 No.	30,057.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover. Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2363 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR REPAIRING CUM MAINTAINANCE OF COMMUNITY TOILETS AT MOUZA DHABONI JL. NO- 50,
UNDER CHINGANI BEAT OF ONDA RANGE,PANCHET DIVISION, BISHNUPUR, BANKURA.**

SL NO	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Quarter Average		TOTAL			66.000	SQM	19.00	1254.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,20mm thick plaster. According to PWD Schedule 2017 Page-189/lt.no -1(i)b (3rd corriggen page-49 sl-1)								
	i) OUTER SIDE		1	10.500	2.900	30.450			
			TOTAL			30.450	m²	153.00	4658.85
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]with 1:6 cement mortar,15mm thick plaster. According to PWD Schedule, 2017 Page-189/lt.no -1(i)c (3rd corriggen page-49 sl-1)								
	I)INNER SIDE		1	4.000	2.900	11.600			
						11.600	m²	135.00	1566.00
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (c) 10 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).c (3rd corriggen page-49 sl-1)								
	I) roof slab		1	2.400	1.800	4.320			
	ii)CHAJJA FOR DOOR BOTH SIDE		2	1.250	0.450	1.125			
	iii)CHAJJA FOR WINDOW BOTH SIDE		2	0.750	0.450	0.675			
	iv) stair		3	0.450	1.250	1.688			
			TOTAL			7.808	m²	122.00	952.58
5	Neat cement punning about 1.5mm thick in wall,dado>window sill,floor etc. NOTE:Cement 0.152 cu.m per100 sq.m. According to PWD Schedule 2017 Page-192/lt.no-15								
	i) flooring with dado		1	3.000	2.400	7.200			
	ii) outside dado		1	10.500	0.300	3.150			
	iii) stair		1	1.250	0.750	0.938			
			TOTAL			11.288	sqm	34.00	383.79

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
6	Supplying, Fitting & Fixing 30 mm thick both side prelaminate Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel				
	with 10 mm (5 mmx2) th., 20 mm wide cross PVC sheet as gap insert for top rail and bottom rail sheet to be fitted in the M.S. frame welded/sealed to the styles & rails with 7 mm (5 mm+2 mm) th. x 15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardware as per direction of Engineer-in-Charge. According to PWD Schedule 2017 Page-126/It.no-16				
		1	0.900		1.800
	TOTAL	1.620	sqm	2438.00	3949.56
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion.. According to PWD Schedule 2017 Page-197/It.no-17(a)				
	I) SAME AS PLASTER (INSIDE + OUTSIDE+CHAJJA)	49.858			
	TOTAL	49.858	m²	67.00	3340.49
8	Supplying, fitting and fixing PVC pipes for underground work of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted including cost of all materials, jointing materials, cutting pipes, making threads, cutting trenches upto 1.5 metre below surface in all sort of soil and refilling the same as directed complete in all respect. (Payment will be made on the centre line measurement of the total pipe line including all specials No separate payment will be made for accessories, specials.) According to PWD Schedule 2017 (volume II) Page-13/It.no- 19 II	5.00	m	143.00	715.00

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT (Rs.)
9	Supplying, fitting and fixing cast iron 'P' or 'S' trap conforming to I.S. 3989/2009 and 1729/2002 including lead caulked joints and painting two coats to the exposed surface. (Painting to be paid separately) (A) 'P' Trap (iii) 100 mm . According to PWD Schedule 2017 (volume II)Page-65/It.no- 14 a				
	(A) 'P' Trap (i) 50 mm	1.00	each	507.00	507.00
	(B) 'S' Trap (i) 50 mm	1.00	each	675.00	675.00
10	Suppling, fitting and fixing Wall mounted water closet of white glazed vitreous chinaware of approved make and brand in position complete with necessary nut and bolts (Equivalent to Code No. 20061 or 92065 & Model Studio or Rubbic of Hindware or equivalent.) According to PWD Schedule 2017 (volume II)Page-79/It.no- 5	1.00	each	3988.00	3988.00
11	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (i) 635 mm X 395 mm X 420 mm According to PWD Schedule 2017 (volume II)Page-80/It.no- 6	1.00	each	2869.00	2869.00
12	Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.(a) E.W.C.(i) Plastic (hallow type) black 10/P-81 (S&P)	1.00	each	302.00	302.00
13	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long 10/P-43 (S&P)	1.00	each	59.00	59.00
(1) Sub-total Cost					25220.27
(2) 18% GST, as applicable on sl no 1					4539.65
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					29759.92
(4) Labour welfare cess @1% on sl no 3					297.60
(5) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					892.80
(6) TOTAL AMOUNT (3+4+5)					30950.32
SAY					30950.00
(IN WORDS: THIRTY THOUSAND NINE HUNDRED FIFTY ONLY)					


ANUR MAHATA
 (Reg.-01293) D.O.E.
 Khatra, Bankura


Divisional Forest Officer
 Panchet Division, Bishnupur