



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 59/ Repair of group D Quarter of 2025-26(TD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair of group D Quarter at Chenchuria Mouza, J.L. No.- 70, Qtr. No. B/01/TD-PSC, 01 No. (N23°01'13.30" E087°05'59.50") of Taldangra Beat, Taldangra Range under Panchet Division. (On Contract)

Copy of estimate Enclose

Range	Beat	Mouza	Quantity	Project Cost
Taldangra	Taldangra	Chenchuria Mouza, J.L. No.- 70 Qtr. No. B/01/TD-PSC	01 No.	48,557.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2379 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR MAINTENANCE WORK OF GR-D STAFF QUATAR AT MOUZA CHENCHURIA OF TALDANGRA RANGE
UNDER PANCHETVISION , BISHNUPUR, DIST-BANKURA**

ITEM OF WORK	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Average		TOTAL			53.000	sqm	19.00	1007.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (A) 20 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).a								
			TOTAL			53.000	m²	153.00	8109.00
3	Iron parliamentary hinges conforming to IS 362-1982 fitted and fixed complete with steel screws. (a) 50mm. X 100mm. X 20mm. X 2.24mm. According to PWD Schedule, 2017 page-140/it.no 6 a								
	I)FOOR ALL DOOR		2X5			10.000			
	II)FOR ALL WINDOW		4X8			32.000			
			TOTAL			42.000	Each	66.00	2772.00
4	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete. According to PWD Schedule 2017 Page-145/lt. No-28(i)								
	I)FOR DOOR FRAME (D)		2X1			2.000			
			TOTAL			2.000	Each	233.00	466.00
5	Iron door ring of approved quality fitted and fixed with nut and washer complete.(i)50mm dia. According to PWD Schedule 2017 Page-134/lt.no-24								
	I) FOR WINDOW (W)		4x4			16.000			
			TOTAL			16.000	Each	17.00	272.00
6	(B) Painting with superior quality aluminium paint of approved make and brand including smoothening surface by sand papering etc. on steel surface : (i) one coats. According to PWD Schedule 2017 Page-201/lt.no-3(a)								
	I) FOR GRIL		3	1.720	1.200	6.192			
			TOTAL			6.192	m²	34.00	210.53
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion. According to PWD Schedule 2015 Incorporation of GST Act Page-197/lt.no-17(a)								
	OUTSIDE								
	I) Group -D BUILDING		1	42.000	3.100	130.200			
			TOTAL			130.200	Sq.M	67.00	8723.40

OF ORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
8	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats. According to PWD Schedule 2017 Page-196/lt.no- 10				
	i) bed room celing(sloping roof)	1	3.500	3.300	
	TOTAL	11.550	Sq.M	70.00	808.50
9	Dismantling Orissa pattern W.C. including taking out of base concrete, if necessary, complete. According to PWD Schedule 2017 (volume II)Page-85/lt.no- 6	1.000	each	45.00	45.00
10	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity. According to PWD Schedule 2017 (volume II)Page-37/lt.no- 6 (b)	1.000	each	5128.00	5128.00
11	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (iv) With local hard blackstone variety chips (crusher broken). According to PWD Schedule 2017 Page-26/lt. No-10(iv) (3rd corrigien page-12 sl-33)				
	R.C.C slab	1	1.500	1.500	0.125
	TOTAL	0.281	m³	4888.00	1373.53
12	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m According to PWD Schedule 2017 Page-43/lt. No-40.a(i) (9th corrigien page-1 sl-1)				
	1.2% of total concrete	0.026	M.ton	60433.00	1571.26
13	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (ii) 550 mm X 400 mm size 1/P-41 (S&P)	1.000	each	1383.00	1383.00
14	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap (with vent) 2/P-79 (S&P)	1.000	each	1421.00	1421.00
15	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). 7/P-6 (S&P)	1.000	each	539.00	539.00
16	Supplying, fitting and fixing bib cock or stop cock. (d) (i) Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand). 7/P-6 (S&P)	2.000	each	815.00	1630.00
17	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long. 10/P-43 (S&P)	1.000	each	59.00	59.00

M OF WORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
18	Supplying, fitting and fixing stainless steel sink complete with waste fittings and two coats of painting of C.I. brackets. (a) Sink only (i) 530 mm X 430 mm x 180 mm. 6/P-42 (S&P)	1.000	each	3285.00	3285.00
(A) Civil Cost					38803.22
(B) 5% electrification charge of civil cost					1940.16
(1) Sub-total Cost A+B					40743.38
(2) 18% GST, as applicable on sl no 1					7333.81
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					48077.19
(4) Labour welfare cess @1% on sl no 3					480.77
(5) Cost of civil works including labour welfare cess on sl no. (3+4)					48557.96
(6) Contingency Charge @ 3% is to be considered on Sl. No. - (3)					1442.32
TOTAL AMOUNT (5+6)					50000.28
SAY					50000.00

Rupees Fifty Thousand Only



Divisional Forest Officer
Panchet Division
Bishnupur

*Vetted for amount of Rs-50000/-
(Fifty thousand Only)*

**VETTED
&
Countersigned**

(Signature)
(Dr. S. KULANDAIVEL, I.F.S.)
Chief Conservator of Forests,
Central Circle, West Bengal



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 60/ Repair of group D Quarter of 2025-26(OD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair of group D Quarter at Krishnanagar- Mouza, J.L. No.- 179, QTR No. B/11/OD 01 No. (N23°06'53.86" E87°10'24.15") of Krishnanagar Beat, Onda Range under Panchet Division. (On Contract)

Copy of estimate EnCLOSE

Range	Beat	Mouza & J.L. No.	Quantity	Project Cost
Onda	Krishnanagar	Krishnanagar- Mouza, J.L. No.- 179 QTR No. B/11/OD	01 No.	48,557.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover. Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

**Divisional Forest Officer,
Panchet Division, Bishnupur**

No. 2380(9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

**Divisional Forest Officer,
Panchet Division, Bishnupur**


**ESTIMATE FOR MAINTENANCE WORK OF GR-D STAFF QUATAR AT MOUZA KRISHNANAGAR OF JONDA RANGE
UNDER PANCHETVISION, BISHNUPUR, DIST-BANKURA**

ITEM OF WORK	DESCRIPTION OF ITEM				QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10							
	Average	TOTAL			53.000	sqm	19.00	1007.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (A) 20 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).a							
		TOTAL			53.000	m²	153.00	8109.00
3	Iron parliamentary hinges conforming to IS 362-1982 fitted and fixed complete with steel screws. (a) 50mm. X 100mm. X 20mm. X 2.24mm. According to PWD Schedule, 2017 page-140/lt.no 6 a							
	I)FOOR ALL DOOR	2X5			10.000			
	II)FOR ALL WINDOW	4X8			32.000			
		TOTAL			42.000	Each	66.00	2772.00
4	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete. According to PWD Schedule 2017 Page-145/lt. No-28(i)							
	I)FOR DOOR FRAME (D)	2X1			2.000			
		TOTAL			2.000	Each	233.00	466.00
5	Iron door ring of approved quality fitted and fixed with nut and washer complete.(i)50mm dia. According to PWD Schedule 2017 Page-134/lt.no-24							
	I) FOR WINDOW (W)	4x4			16.000			
		TOTAL			16.000	Each	17.00	272.00
6	(B) Painting with superior quality aluminium paint of approved make and brand including smoothening surface by sand papering etc. on steel surface : (i) one coats. According to PWD Schedule 2017 Page-201/lt.no-3(a)							
	I) FOR GRIL	3	1.720	1.200	6.192			
		TOTAL			6.192	m²	34.00	210.53
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer in Ground floor (Two Coat) a) Normal Acrylic Emulsion. According to PWD Schedule 2015 Incorporation of GST Act Page-197/lt.no-17(a)							
	OUTSIDE							
	I) Group -D BUILDING	1	42.000	3.100	130.200			
		TOTAL			130.200	Sq.M	67.00	8723.40

OF JRK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
8	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats. According to PWD Schedule 2017 Page-196/lt.no- 10				
	i) bed room celing(sloping roof)	1	3.500	3.300	
	TOTAL	11.550			
		11.550	Sq.M	70.00	808.50
9	Dismantling Orissa pattern W.C. including taking out of base concrete, if necessary, complete. According to PWD Schedule 2017 (volume II)Page-85/lt.no- 6	1.000	each	45.00	45.00
10	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity. According to PWD Schedule 2017 (volume II)Page-37/lt.no- 6 (b)	1.000	each	5128.00	5128.00
11	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (iv) With local hard blackstone variety chips (crusher broken). According to PWD Schedule 2017 Page-26/lt. No-10(iv) (3rd corrigien page-12 sl-33)				
	R.C.C slab	1	1.500	1.500	0.125
	TOTAL	0.281			
		0.281	m³	4888.00	1373.53
12	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m According to PWD Schedule 2017 Page-43/lt. No-40.a(i) (9th corrigien page-1 sl-1) 1.2% of total concrete				
		0.026	M.ton	60433.00	1571.26
13	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (ii) 550 mm X 400 mm size 1/P-41 (S&P)	1.000	each	1383.00	1383.00
14	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap (with vent) 2/P-79 (S&P)	1.000	each	1421.00	1421.00
15	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). 7/P-6 (S&P)	1.000	each	539.00	539.00
16	Supplying, fitting and fixing bib cock or stop cock. (d) (i) Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand). 7/P-6 (S&P)	2.000	each	815.00	1630.00
17	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long. 10/P-43 (S&P)	1.000	each	59.00	59.00


NO OF WORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
18	Supplying, fitting and fixing stainless steel sink complete with waste fittings and two coats of painting of C.I. brackets. (a) Sink only (i) 530 mm X 430 mm x 180 mm. 6/P-42 (S&P)	1.000	each	3285.00	3285.00
(A) Civil Cost					38803.22
(B) 5% electrification charge of civil cost					1940.16
(1) Sub-total Cost A+B					40743.38
(2) 18% GST, as applicable on sl no 1					7333.81
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					48077.19
(4) Labour welfare cess @1% on sl no 3					480.77
(5) Cost of civil works including labour welfare cess on sl no. (3+4)					48557.96
(6) Contingency Charge @ 3% is to be considered on Sl. No. - (3)					1442.32
TOTAL AMOUNT (5+6)					50000.28
SAY					50000.00

Rupees Fifty Thousand Only


Divisional Forest Officer
Panchet Division
Bishnupur

*vetted for amount of Rs. 50,000/-
(Fifty thousand only)*

**VETTED
&
Countersigned**


(Dr. S. KULANDAIVEL, I.F.S.)
Chief Conservator of Forests,
Central Circle, West Bengal



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 61/ Repair of group D Quarter of 2025-26(JP)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair of group D Quarter at Jangalmahal Mouza, J.L. No.- 85, QTR No. B/11/OD 01 No. of Joypur Beat, Joypur Range under Panchet Division. (On Contract)

Copy of estimate Enclose

Range	Beat	Mouza	Quantity	Project Cost
Joypur	Joypur	Jangalmahal Mouza, J.L. No.- 85 Qtr. No. 57(B)/JP	01 No.	48,557.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2381 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur


**ESTIMATE FOR MAINTENANCE WORK OF GR-D STAFF QUATAR AT MOUZA JANGALMAHAL OF JOYPUR RANGE
UNDER PANCHETVISION . BISHNUPUR, DIST-BANKURA**

ITEM OF WORK	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Average		TOTAL			53.000	sqm	19.00	1007.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (A) 20 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).a								
			TOTAL			53.000	m ²	153.00	8109.00
3	Iron parliamentary hinges conforming to IS 362-1982 fitted and fixed complete with steel screws. (a) 50mm. X 100mm. X 20mm. X 2.24mm. According to PWD Schedule, 2017 page-140/it.no 6 a								
	I)FOOR ALL DOOR		2X5			10.000			
	II)FOR ALL WINDOW		4X8			32.000			
			TOTAL			42.000	Each	66.00	2772.00
4	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete. According to PWD Schedule 2017 Page-145/lt. No-28(i)								
	I)FOR DOOR FRAME (D)		2X1			2.000			
			TOTAL			2.000	Each	233.00	466.00
5	Iron door ring of approved quality fitted and fixed with nut and washer complete.(i)50mm dia. According to PWD Schedule 2017 Page-134/lt.no-24								
	I) FOR WINDOW (W)		4x4			16.000			
			TOTAL			16.000	Each	17.00	272.00
6	(B) Painting with superior quality aluminium paint of approved make and brand including smoothening surface by sand papering etc. on steel surface : (i) one coats. According to PWD Schedule 2017 Page-201/lt.no-3(a)								
	I) FOR GRIL		3 1.720 1.200			6.192			
			TOTAL			6.192	m ²	34.00	210.53
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion. According to PWD Schedule 2015 Incorporation of GST Act Page-197/lt.no-17(a)								
	OUTSIDE								
	I) Group -D BUILDING		1 42.000 3.100			130.200			
			TOTAL			130.200	Sq.M	67.00	8723.40

Sl. NO. OF WORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
8	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats. According to PWD Schedule 2017 Page-196/It.no- 10				
	i) bed room celing(sloping roof)	1	3.500	3.300	11.550
	TOTAL	11.550	Sq.M	70.00	808.50
9	Dismantling Orissa pattern W.C. including taking out of base concrete, if necessary, complete. According to PWD Schedule 2017 (volume II)Page-85/It.no- 6	1.000	each	45.00	45.00
10	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity. According to PWD Schedule 2017 (volume II)Page-37/It.no- 6 (b)	1.000	each	5128.00	5128.00
11	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (iv) With local hard blackstone variety chips (crusher broken). According to PWD Schedule 2017 Page-26/It. No-10(iv) (3rd corrigien page-12 sl-33)				
	R.C.C slab	1	1.500	1.500	0.125
	TOTAL	0.281	m ³	4888.00	1373.53
12	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m According to PWD Schedule 2017 Page-43/It. No-40.a(i) (9th corrigien page-1 sl-1)				
	1.2% of total concrete	0.026	M.ton	60433.00	1571.26
13	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (ii) 550 mm X 400 mm size 1/P-41 (S&P)	1.000	each	1383.00	1383.00
14	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap (with vent) 2/P-79 (S&P)	1.000	each	1421.00	1421.00
15	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). 7/P-6 (S&P)	1.000	each	539.00	539.00
16	Supplying, fitting and fixing bib cock or stop cock. (d) (i) Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand). 7/P-6 (S&P)	2.000	each	815.00	1630.00
17	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long. 10/P-43 (S&P)	1.000	each	59.00	59.00


Sl. No. OF WORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
18	Supplying, fitting and fixing stainless steel sink complete with waste fittings and two coats of painting of C.I. brackets. (a) Sink only (i) 530 mm X 430 mm x 180 mm. 6/P-42 (S&P)	1.000	each	3285.00	3285.00
(A) Civil Cost					38803.22
(B) 5% electrification charge of civil cost					1940.16
(1) Sub-total Cost A+B					40743.38
(2) 18% GST, as applicable on sl no 1					7333.81
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					48077.19
(4) Labour welfare cess @1% on sl no 3					480.77
(5) Cost of civil works including labour welfare cess on sl no. (3+4)					48557.96
(6) Contingency Charge @ 3% is to be considered on Sl. No. – (3)					1442.32
TOTAL AMOUNT (5+6)					50000.28
SAY					50000.00

Rupees Fifty Thousand Only


Divisional Forest Officer
Panchet Division
Bishnupur

*Vetted for amount of Rs. 50,000/-
(Fifty thousand only)*

VETTED
&
Countersigned


(Dr. S. KULANDAIVEL, I.F.S.)
Chief Conservator of Forests,
Central Circle, West Bengal



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail: dfopanbis-wb@nic.in,
Website: www.bankuraforest.in



Quotation No. 62/ Repair of group D Quarter of 2025-26(BKD)

Dated, Bishnupur, the: 31 / 12 / 2025

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafide experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Shri Abhijit Kar, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

Quotation for Repair of group D Quarter at Uporsole Mouza, J.L. No.- 156 (930), Qtr. No. 7/UPS, 01 No. (N22°58.822' E087°24.258') of Uporsole Beat, Bankadaha Range under Panchet Division. (On Contract)

Copy of estimate EnCLOSE

Range	Beat	Mouza	Quantity	Project Cost
Bankadaha	Uporsole	Uporsole Mouza, J.L. No.- 156 (930) Qtr. No. 7/UPS	01 No.	48,557.00

CONDITIONS

1. The Quotation should be submitted in **sealed cover**. **Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2. The Contractor should **quote the rates, Percentage (%) in figures as well as in words.**
3. The materials to be supplied must be approved by the concerned Authority.
4. If any defects or issues are found with the supplied materials, it will likely need to be replaced with materials that meet the necessary standards. This is to be ensured that the safety and quality of the materials being used in whatever application they are intended for meets Standard specifications as per PWD.
5. **The Contractors should submit Income-Tax, Sales Tax and Professional Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.**
6. Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any or all of the quotations without assigning any reason whatsoever.
7. **The estimated rate is inclusive of all Taxes. The quotationer should quote their rate accordingly.**
8. **Bill has to be submitted with detailed break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.**
9. **For complying with Mahatma-Shree, the employment should first be offered to "Job Card Holders" from the fringe villagers and L1 Bidders/Contractors getting Work Order have to compulsorily submit the details as per Annexure-VI, as mandated under the scheme.**
10. Sealed Quotation will be received up to **14/01/2026 & Opened on 15/01/2026 at 11:30 A.M.**
11. The Bidders should submit PAN- Aadhaar link screen shot for authentication of PAN-Aadhaar being already linked.

Divisional Forest Officer,
Panchet Division, Bishnupur

No. 2382 (9)/02-08

Dated, Bishnupur, the: 31 / 12 / 2025

Copy forwarded for information to and wide circulation to:

1. The Chief Conservator of Forests, Central Circle, West Bengal.
2. The District Magistrate & Collector, Bankura
3. The Divisional Forest Officer, Bankura South Division, Bankura North Division & Working Plan (South) Division -II
4. The Sub- Divisional Officer, Bishnupur.
5. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
6. The All Range Officers, Panchet Division with request to affix in the Range Notice board for wide publication.
7. Head Clerk, Panchet Division for Office Notice Board.
8. Account & Budget Section of Panchet Division.
9. Notice Board at Division Office.

Divisional Forest Officer,
Panchet Division, Bishnupur

**ESTIMATE FOR MAINTENANCE WORK OF GR-D STAFF QUATAR AT MOUZA UPORSOLE OF BANKADAHA RANGE
UNDER PANCHETVISION , BISHNUPUR, DIST-BANKURA**

ITEM OF WORK	DESCRIPTION OF ITEM					QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. According to PWD Schedue , 2017 Page-11/lt. No-10								
	Average		TOTAL			53.000	sqm	19.00	1007.00
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar. (A) 20 mm thick plaster According to PWD Schedule 2017 Page-189/lt. No-1.(ii).a								
			TOTAL			53.000	m²	153.00	8109.00
3	Iron parliamentary hinges conforming to IS 362-1982 fitted and fixed complete with steel screws. (a) 50mm. X 100mm. X 20mm. X 2.24mm. According to PWD Schedule, 2017 page-140/it.no 6 a								
	I)FOOR ALL DOOR		2X5			10.000			
	II)FOR ALL WINDOW		4X8			32.000			
			TOTAL			42.000	Each	66.00	2772.00
4	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete According to PWD Schedule 2017 Page-145/lt. No-28(i)								
	I)FOR DOOR FRAME (D)		2X1			2.000			
			TOTAL			2.000	Each	233.00	466.00
5	Iron door ring of approved quality fitted and fixed with nut and washer complete.(i)50mm dia. According to PWD Schedule 2017 Page-134/lt.no-24								
	I) FOR WINDOW (W)		4x4			16.000			
			TOTAL			16.000	Each	17.00	272.00
6	(B) Painting with superior quality aluminium paint of approved make and brand including smoothening surface by sand papering etc. on steel surface : (i) one coats. According to PWD Schedule 2017 Page-201/lt.no-3(a)								
	I) FOR GRIL		3	1.720	1.200	6.192			
			TOTAL			6.192	m²	34.00	210.53
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer In Ground floor (Two Coat) a) Normal Acrylic Emulsion. According to PWD Schedule 2015 Incorporation of GST Act Page-197/lt.no-17(a)								
	OUTSIDE								
	I) Group -D BUILDING		1	42.000	3.100	130.200			
			TOTAL			130.200	Sq.M	67.00	8723.40

OF JRK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
8	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats. According to PWD Schedule 2017 Page-196/lt.no- 10				
	i) bed room celing(sloping roof)	1	3.500	3.300	11.550
	TOTAL	11.550	Sq.M	70.00	808.50
9	Dismantling Orissa pattern W.C. including taking out of base concrete, if necessary, complete. According to PWD Schedule 2017 (volume II) Page-85/lt.no- 6	1.000	each	45.00	45.00
10	Supplying P.V.C. water storage tank of approved quality with closed top with lid (Black) - Multilayer (b) 1000 litre capacity. According to PWD Schedule 2017 (volume II) Page-37/lt.no- 6 (b)	1.000	each	5128.00	5128.00
11	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (iv) With local hard blackstone variety chips (crusher broken). According to PWD Schedule 2017 Page-26/lt. No-10(iv) (3rd corrigien page-12 sl-33)				
	R.C.C slab	1	1.500	1.500	0.125
	TOTAL	0.281	m³	4888.00	1373.53
12	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor/upto 4 m According to PWD Schedule 2017 Page-43/lt. No-40.a(i) (9th corrigien page-1 sl-1)				
	1.2% of total concrete	0.026	M.ton	60433.00	1571.26
13	Wash basin vitreous china of approved make (without fittings) supplied, fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. (ii) 550 mm X 400 mm size 1/P-41 (S&P)	1.000	each	1383.00	1383.00
14	Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc. (a) With 'P' trap (with vent) 2/P-79 (S&P)	1.000	each	1421.00	1421.00
15	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand). 7/P-6 (S&P)	1.000	each	539.00	539.00
16	Supplying, fitting and fixing bib cock or stop cock. (d) (i) Chromium plated angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand). 7/P-6 (S&P)	2.000	each	815.00	1630.00
17	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (ii) 750 mm long. 10/P-43 (S&P)	1.000	each	59.00	59.00

M OF WORK	DESCRIPTION OF ITEM	QTY	UNIT	RATE(Rs.)	AMOUNT(Rs.)
18	Supplying, fitting and fixing stainless steel sink complete with waste fittings and two coats of painting of C.I. brackets. (a) Sink only (i) 530 mm X 430 mm x 180 mm. 6/P-42 (S&P)	1.000	each	3285.00	3285.00
(A) Civil Cost					
(B) 5% electrification charge of civil cost					38803.22
(1) Sub-total Cost A+B					1940.16
(2) 18% GST, as applicable on sl no 1					40743.38
(3) Cost of civil works excluding labour welfare cess sl no. (1+2)					7333.81
(4) Labour welfare cess @1% on sl no 3					48077.19
(5) Cost of civil works including labour welfare cess on sl no. (3+4)					480.77
(6) Contingency Charge @ 3% is to be considered on Sl. No. - (3)					48557.96
TOTAL AMOUNT (5+6)					1442.32
SAY					50000.28
					50000.00

Rupees Fifty Thousand Only



Divisional Forest Officer
Panchet Division
Bishnupur

*vetted for amount of Rs. 50,000/-
(Fifty thousand only)*

VETTED
&
Countersigned

(Dr. S. KULANDAIWEL, I.F.S.)
Chief Conservator of Forests,
Central Circle, West Bengal